

11-12

2-100791

14
R

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 11 1993

1-11-93

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-155-20,686-0000
S2 NE NE, SECTION 14 TOWNSHIP 23 RANGE 10W

OPERATOR LICENSE # 5141 4120 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Zenith Drilling Corp.
NAME & 100 N. Broadway, #505
ADDRESS Wichita, KS 67202

LEASE NAME: Lang #1
COUNTY: Reno
WELL TOTAL DEPTH: 3670' 119.28

PIPE: 4-1/2" @ 3669'/125 sx

SURFACE CASING: 8-5/8" @ 242'/225 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 11:00a DAY: 12 MONTH: 11 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Vernon Dunce
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand 50' into open hole or above top perms w/4 sx cmt
- shoot & pull 4-1/2" to 1425' - pump 35 sx - pull 4-
1/2" to 900' - pump 35 sx cmt - pull pipe to 300' &
circulate.

PLUGGING PROPOSAL RECEIVED BY: Phil

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1:00p DAY: 12 MONTH: 11 YEAR: 1992

ACTUAL PLUGGING REPORT:
Sanded to 3000' & dumped 4 sx cmt w/bailer - shot
& pulled 2396' of 4-1/2" to 1425' & pumped 35 sx cmt
& 100 lbs hulls - pulled 4-1/2" to 900' pumped 35 sx
cmt & 100 lbs hulls - pulled 4-1/2" to 300' & circ -
pulled pipe & topped off well.

REMARKS: Allied #3483 60/40 4% gel

INVOICED
DID OBSERVE THIS PLUGGING.

DATE 1-25-93

INV. NO. 37232

J. L. Sanders
J. L. Sanders (AGENT)

aw