

2 040139

15-155-01832-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

N/A

R

SWSE, SEC. K, T 23 S, R 10

571 feet from N/E section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Estey Well # A-2

Operator: Cities Service Oil & Gas County Reno

122.04

Name & Address 800 Sutton Place

Well Total Depth 3755 feet

209 E Williams

Conductor Pipe: Size \_\_\_\_\_ feet

Wichita Ks 67202

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clark Corp.

License Number 6505

Address Medicine Lodge Ks.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Brett Smith

(company name) Cities Service (phone) \_\_\_\_\_

were:

5 1/2 3477

OH 3747-55

Reda Pump stuck at 2400'

RECEIVED  
STATE CORPORATION COMMISSION

DEC 07 1984

CONSERVATION DIVISION  
Wichita, Kansas

12-7-84

Plugging Proposal Received by St. A. Guai  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 1300 Day: 3 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Sanded back to bottom from 2400 to 2326

and dumped 5 sack of cement on sand with a dump  
bailer. Shot off casing at 1700' and spotted a 20 sack  
plug of cement thru casing. Pulled casing to 1214' and  
spotted 20 sacks of cement. Pulled casing to 565' and  
spotted 20 sacks of cement. Pulled casing to 246' and

Remarks: circulated down casing, up to the surface, top of cement 30'  
down.  
(If additional description is necessary, use BACK of this form.)

Allied Cementing 38486.

(did not) observe this plugging.

INVOICED

DATE 12-18-84

WC

Signed St. A. Guai  
(TECHNICIAN)

INV NO. 5991

FORM CP-2/3  
Rev. 01-84