



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. W. C. Goodwin of Atlantic Richfield Company has this date requested permission to plug the following described well:

Mr. Atlantic Richfield Co. guarantees payment of the plugging fee.

Operator's full Name: Atlantic Richfield Company

Complete Address: Box 849, Great Bend, Kansas 67530

Lease Name: Community Selma Seyfert "B" Well No. # 2

Location: SW SW SW Sec. 21 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3352 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Charles Duvall was instructed to plug the well as follows:

10 3/4" 118' Cwc.

No pipe recovery. Well previously squeezed.

Run tubing to 3350' & displaced 20 sax cement. Pulled 4 joints

tubing & circulated hole with mud to 300'. Pulled remaining tubing,

set plug, & displaced 80 sax cement with Halliburton Cementing Company's

pump truck, cementing from 300' to Very truly yours,

base of cellar.

Don Duvall  
Conservation Division Agent