

15-055-10062-0000

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1966  
4-15-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Amarillo Nat. Gas Co. has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Amarillo Natural Gas Company

Complete Address: Box 506, Liberal, Kansas

Lease Name: Collins Well No. 1

Location: SE SE NE Sec. 29 Twp. 22 Rge. 33 (E) (W)

County Finney Total Depth 4476' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 396' Circulated w/ cement. 4 1/2" to 4476' cemented.

Top of Perforations 4448' Plug bottom w/ 15 sacks cement.

Top of cement 4300' Mud 4300' to 450' #0

Spotted 35 sacks cement 450' to 350' Mud 350' to 45'

Plug, Hulls & 15 sacks cement 45' to 0

Very truly yours,

Edgar J. Jones  
Conservation Division Agent