

State of Kansas



15-055-10167-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Morton of Texaco Inc. has this
date requested permission to plug the following described well:

Mr. Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: R.L. Becker Well No. 1

Location: SE NE SE Sec. 29 Twp. 22 Rge. 33 (E) (W)

County Finney Total Depth 4825' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morton was instructed to plug the well as follows:

8 5/8" to 387' circulated w/ cement, 4 1/2" to 4825' cemented.

Top perforations 4730' Plug bottom w/ 15 sacks cement.

Top of cement 4600' Mud 4600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 380'

Spotted 35 sacks cement 380' to 280' Mud 280' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent