



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Texaco has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: Box 2420, Tulsa, Oklahoma

Lease Name: Garden City "D" NCT-2 Well No. 1

Location: C SE NW Sec. 29 Twp. 22 Rge. 33 XX (E)(W)

County: Finney Total Depth 4852' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

9 5/8" to 514' circulated w/ cement. 7" to 4850' cemented.

Top perforations 2503' Plug bottom w/ 25 sacks cement.

Top of cement 2310' Mud 2310' to 514'

Spot 40 sacks cement 514' to 414' Mud 414' to 200'

Spot 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent