



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 26 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Richard of Lonita Oil Corp. Inc. has this date requested permission to plug the following described well:

Mr. Richard guarantees payment of the plugging fee.

Operator's full Name: Lonita Oil Corp. Inc.

Complete Address: 704 Bitting Bldg. Wichita, Kansas

Lease Name: Damme Well No. A-3

Location: SW NW SW Sec. 33 Twp. 22S Rge. 33 (E) (W)

County Finney Total Depth 4920 Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Richard was instructed to plug the well as follows:

8 5/8"-386' Circulated w/cement.

Mud 4920' to 2700' Spotted 110 Sax. cement at 2700' to 2370'

Mud 2370' to 700' Spotted 25 Sax. cement 700' to 625'

Mud 625' to 385' Spotted 25 Sax. cement 385' to 310'

Mud 310' to 40' Plug, Hulls, 15 Sax. cement 40' to 0'

Very truly yours,

[Signature]
 Conservation Division Agent