



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lange of R.W. Lange has this

date requested permission to plug the following described well:

Mr. Lange guarantees payment of the plugging fee.

Operator's full Name: R.W. Lange

Complete Address: Box 1034, Garden City, Kansas

Lease Name: Rooney Well No. 1

Location: 660' S & 660' E of NW/4 Sec. 4 Twp. 22 Rge. 35 (E)(W)

County: Kearny Total Depth 4600' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lange was instructed to plug the well as follows:

8 5/8" to 823' circulated w/ cement. 2 3/8" tubing w/ Packer to 4389'

Top perforations 4530' Plug bottom w/ 15 sacks cement

Top of cement 4400' Mud 4400' to 800'

Bridge & 30 sacks cement 800' to 700' Mud 700' to 40'

Bridge & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar A. Eves
Conservation Division Agent