



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Hall of Thor Corporation has this date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Thor Corporation

Complete Address: Box 897 Great Bend, Kansas

Lease Name: Rooney Well No. 1

Location: C NW NW Sec. 4 Twp. 22 Rge. 35 (E)(W)

County Kearny Total Depth 5085 { Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

8 5/8"-823' Circulated w/cement. 4 1/2"-4599' Cemented.

Perforations 4463' to 4505'

Sand hole from bottom up 4450' 10 Sax.cement 4450' to 4350'

Mud 4350' to 800' 35 Sax.cement 800' to 700'

Mud 700' to 50' Rock Bridge 50' to 40'

15 Sax.cement 40' to 0

Very truly yours,

[Signature]
 Conservation Division Agent