



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1972  
CONSERVATION DIVISION  
Wichita, Kansas

12-19-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Petroleum Inc. has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 W. Douglas, Wichita, Kansas

Lease Name: Williamson Well No. 1

Location: C SW SE Sec. 4 Twp. 22 Rge. 35 XX (E) (W)

County: Kearny Total Depth 5050' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

8 5/8" to 869' circulated w/ cement. Mud 5050' to 850'

Spot 35 sacks cement 850' to 750' Mud 750' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Lives  
Conservation Division Agent