



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-155-01491-0000 August 5, 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

AUG 13 1963

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. George Klein of Messman-Rinehart Oil Co. has this

date requested permission to plug the following described well:

Mr. Klein guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Co.

Complete Address: 518 Petroleum Bldg., Wichita, Kansas

Lease Name: Weber Well No. 1

Location: SE SE SE Sec. 12 Twp. 23 Rge. 10 (E) (W) X

County Reno Total Depth 3947' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Klein was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 250'. Push

plug and 1/4 sack hulls to 250' and cement with 20 sacks

through drill pipe. Fill hole with mud to 40'. Push plug

and 1/4 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Alfred L. ...
 Conservation Division Agent