


15-009-03053 [0001]

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Solar Oil Company

Complete Address 1117 Union National Building Wichita, Kansas 67202

Lease Name K. Schartz Well No. 7

Location SW NE NE Sec. 18 Twp. 16 Rge. (E) (W) 11

County Barton Total Depth 3271

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 312 N Day 11 Month 8 Year 1969

The above well was plugged as follows:

Total Depth 3271' 8 5/8 csg set at 706' cwc

5 1/2 csg set at 3226' cw 125 sk cmt.

5 1/2 csg PBD 2945' and perf. (~~2826-2982~~)

Filled 5 1/2 csg W/sd (~~2800-2945~~) Dumped 5 sk cmt W/dump bailer. (~~2760-2800~~)

Cutoff and recovered 2215' of 5 1/2 csg.

Mid to 400' set rock bridge (375-400)

Filled with 5 yds readymix cmt. (0-375)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 8/12/69

INV. NO. 284-W