

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-009-19255-0000

RECEIVED
STATE CORPORATION COMMISSION

AUG 8 1961

CONSERVATION DIVISION
Wichita, Kansas

8-8-61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Boston

Location: Ne Ne Sw Sec. 18 Twp. 16 Rge. 11 (E) _____ (W) _____

Name of Field: _____ Total Depth: 3336

I have this date completed supervision of plugging of:

Lease Name: Hoffman Well No. B³

Operator's Full Name: N.C.R.A.

Complete Address: 305 Rule Bend - Wichita Kans

Plugging Contractor Ace Pipe Pulling

Address: Great Bend Kans. License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4 P.M. Day 29 Month July Year 1961

The above well was plugged as follows:

Total depth - 3336' -
Spud to 3315' topped with 5000 lbs cement with dump bars
found no surface pipe in hole with 5 1/2" pipe full of holes
from 200' down. Shot 5 1/2" at 1310' and pulled same to
1600' and circulated with 2800 lbs gel mud, pulled 5 1/2" to 400'
and displaced 1000 lbs cement with pump truck. Pulled 5 1/2" out
of hole, holed mud down to 40' built back bridge and displaced
1000 lbs cement. Cement and mud job by Able Cementing Co.

Signed: Robert P. Leiker
Conservation Division Agent

Reviewed: _____
Field Supervisor

Remarks:

INVOICED

DATE 8/14/61

INV. NO. 3485-W