

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966
6-20-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.Complete Address: R. R. # 2, Great Bend, KansasLease Name Werner Unit Well No. # 1Location NE SE Sec. 17 Twp. 30 Rge. 9 (E) (W) WCounty Kingman Total Depth 4319'Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.Address: Box 562, Great Bend, Kansas License No. 574Operation Completed: Hour 5:30PM Day 15th Month June Year 1966

The Above well was plugged as follows:

209' of 8 5/8" surface pipe, cemented with 200 sacks. 4310' of 5 1/2" long
string, cemented with 125 sacks. This is an open hole. Bottom of the hole
was sanded to 4293', and cemented with 5 sacks, through the dump bailer.
3246' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 200', rock bridge from 200' to 190', and cemented with
25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30',
and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 6/20/66INV. NO. 3413-WSigned: Archie Elving
Well Plugging Supervisor