

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1965
11-19-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Deppenbusch Unit Well No. # 1

Location NW SW NW Sec. 17 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4441'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:00PM Day 17th Month Nov. Year 1965

The Above well was plugged as follows:

213' of 8 5/8" surface pipe, cemented with 200 sacks. 4436' of 5 1/2" long
string, cemented with 125 sacks. Plug back to 4385'. Top perforation
4336'. Bottom of the hole was sanded to 4320', and cemented with 5 sacks,
through the dump bailer. 1400' of 5 1/2" long string was recovered from the
hole. Hole was bailed down to 210', rock bridge from 210' to 200', and
cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 11/19/65
INV. NO. 2221-W