

KANSAS

⁷¹⁰ STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1966
8-11-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Deppenbusch "F" Well No. # 1

Location SE NE SW Sec. 23 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No.

Operation Completed: Hour 6:00PM Day 10th Month August Year 1966

The Above well was plugged as follows:

206' of 8 5/8" surface pipe, cement circulated. Hole was filled with
drilling mud to 200', 1st cementing plug, bridged with 2 sacks of dry
cement and 1/2 sack of hulls on fluid at 200', and cemented with 23 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and
cemented with 9 sacks to the base of the cellar. Rat and mouse holes
bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8/11/66

INV. NO. 3435-W