

WELL PLUGGING RECORD

All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County. Sec. 12 Twp. 23 Rge. 10 (E)W (W)

Location as "NE/CNW%SW%" or footage from lines SW SE SW

Lease Owner West Supply Co., Inc.

Lease Name Weideroder A #2 Well No.

Office Address Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 11-6-58 19

Plugging completed 11-14-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample

Producing formation Depth to top Bottom Total Depth of Well 3765 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	162'	none
				7"	3746'	2995'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3765' and found it open.
Filled w/sand to 3700' and dumped 5 sacks of cement with bailer. Pulled 7" to approximately 1700' and circulated with 20 sacks of gel mud. Pulled rest of casing, cleared hole and bailed mud to 170', set rock bridge to 160' and dumped 30 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 15 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1958

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE CONSERVATION DIVISION
I, Noel J. Knight (employee of owner) or (Notary Public) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 58
Thomas V. Dwyer
Notary Public.

My commission expires 9-27-62

PLUGGING
FILE SEC 12 T 23 R 10W
BOOK PAGE 131 LINE 19

WELL RECORD

Partnership

Company Cities Service Oil Co. & Lion Oil & Refining Co. Well No. 2 Farm Weideroder "A"
 Location 330' North and 965' West of 1/4 Corner Sec. 12 T. 23 R. 10W
 Elevation 1757 County Reno State Kansas
 Drig. Comm. January 12, 1943 Contractor Corbett-Barbour Drilling Company
 Drig. Comp. February 1, 1943 Acid None
 T. D. 3764' Initial Prod. Physical Potential: 297 oil, 0 water, 24 hours

CASING RECORD:

10-3/4" @ 162' con. 150 sz Lone Star
 7" @ 3746' con. 75 sz Ash Grove

Set 31' of 5 1/2" liner (bottom 7' perforated) at 3764.

FORMATION RECORD:

sand	0-45
sand & red bed	162
red bed & shells	420
anhydrite	460
shale & shells	1270
red bed & shells	1500
anhydrite	1340
shale & shells	1715
anhydrite	1775
broken lime	1785
lime & sand	1545
lime broken	1740
sand	1743
lime	1750
lime & shale	1623
lime	1870
broken lime	1970
lime	2080
lime & shale	2215
lime	2245
broken lime & shale	2390
shale & lime	2500
lime w/ streaks shale	2570
lime & shale	2687
lime	2710
shale	2750
lime	3085
lime & shale	3249
shale & lime	3294
lime	3577
chert & shale	3621
chert & lime	3636
lime & shale w/ streaks chert	3657
shale	3740

shale & lime	3754
chert	3761
chert & lime	3765

3765 Rot. T. D. = 3764 B. L. H.

Corr. Top Viola	3753'
Penetration	11'
Total Depth	3764'

Loaded hole with 300' water before drilling shoe. Hole filled 300' to 1500' (1200') in 1 1/2 hours. 2000' fluid in 15 hours.

Slope Test (Acid bottle):

500'	OK
1000'	OK
2000'	0°
2800'	0°
3550'	0°

RECEIVED
 STATE CORPORATION COMMISSION

SEP 25 1958

PLUGGING
 FILE SEC. 12 T. 23 R. 10W
 BOOK PAGE 131 LINE 19


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

15-155-83184-0000

CITIES SERVICE OIL CO-LION OIL&REFG.CO.
Weideroder "A" No. 2.

SEC. 12 T. 23 R. 10 W
SW SE SW
330' N 965' W S 1/4 Cor.

County. Reno



Total Depth. 3765=3764 SLM
Comm. 1-12-43 Comp. 2-1-43
Shot or treated. None
Contractor. Corbett-Barbour Drlg.Co.
Issued. 3-27-43

CASING:
10 3/4" 162' Cem.
7" 3746' Cem.
Set 31' of 5 1/2" liner (btm 7' perf.) @ 3764'

Elevation.

Production. Phy. Pot. 297 B.

Figures Indicate Bottom of Formations. No wtr

sand	0-45
sand & red bed	162
red bed & shells	420
anhydrite	460
shale & shells	1270
red bed & shells	1300
anhydrite	1340
shale & shells	1415
anhydrite	1475
lime brkn	1485
lime & sand	1545
lime brkn	1740
sand	1743
lime	1750
lime & shale	1828
lime	1870
lime brkn	1970
lime	2080
lime & shale	2215
lime	2245
lime brkn & shale	2390
shale & lime	2500
lime w/strks shale	2570
lime & shale	2687
lime	2710
shale	2750
lime	3088
lime & shale	3249
shale & lime	3294
lime	3577
chert & shale	3621
chert & lime	3636
lime & shale w/strks	
chert	3657
shale	3740
shale & lime	3754
chert	3761
chert & lime	3765

3765 Rot. TD=3764 SLM
Total Depth.

Corr. Top Viola 3753
Penetration 11

Loaded hole w/300' wtr before
drlg shoe. Hole filled
300' to 1500' (1200')
in 1 1/2 hrs. 2000' fluid in
15 hrs

STATE CO. CONSERVATION DIVISION

NOV 3 1958

CONSERVATION DIVISION
Wichita, Kansas