

15-009-202500000

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1970

CONSERVATION DIVISION
Wichita, Kansas


12-24-70

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 24 Twp. 16 Rge. 11 (E) (W)x
Location as "NE/CNW&SW" or footage from lines SW SW SE
Lease Owner Petroleum Management Inc.
Lease Name Homolka Well No. #1
Office Address Box 922, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 10-28-70 19
Application for plugging approved 19
Plugging commenced 12-19-70 19
Plugging completed 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Donald Truman
Producing formation Depth to top Bottom Total Depth of Well 3380' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"	3372'	1716.10'
				8 /58"	207'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 2950'. Mixed and ran 4 sacks cement thru dump
hailer.
Squeezed hole with 3 sacks hulla - 20 sacks gel. Released plug and displaced with
100 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.



(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

Subscribed and Sworn to before me this 23 day of December, 1970

My commission expires 24 October 1972
Sidney D. Miller
Notary Public.

AUG 12 1968

DRILLERS LOG

No. 1 Homolka

CASING RECORD:	COMPANY:	Petroleum Management, Inc.	DESCRIPTION:
8 5/8" @ 207'	CONTRACTOR:	Red Tiger Drilling Company	SW SW SE
w/210 sx cement	COMMENCED:	July 30, 1968	24-16S-11W
4 1/2" @ 3372'	COMPLETED:	August 7, 1968	Barton Co.,
w/100 sx cement			Kansas
TOTAL DEPTH: 3380'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, pyrite, sand and shale	0	208	
Shale	208	260	
Sand and pyrite	260	355	
Red Bed	355	704	
Anhydrite	704	730	
Shale	730	810	
Shale and shells	810	1430	
Lime and shale	1430	1800	
Lime	1800	1955	
Lime and shale	1955	2890	
Lime	2890	2936	
Heebner	2936	2945	
Shale	2945	3040	
Lime	3040	3054	
Lansing Kansas City	3054	3075	
Lime	3075	3340	
Lime and shale	3340	3351	
Conglomerate	3351	3355	
Arbuckle	3355	3380	

RECEIVED
STATE CORPORATION COMMISSION
OCT 29 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 9th day of August 1968;

Betty M. Maloney
Notary Public

My Commission Expires: