

QF

15-009-19253-0000

Strike out upper line when reporting plugging off formations.

NORTH

24

o

**Locate well correctly on above
Section Plat**

BARTON

County. Sec. 24 Twp. 16 Rge. (E) 11 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE NE SE $\frac{1}{2}$

Lease Owner.....SHELL OIL CO., INC.

Lease Name J. L. HOMOLKA

Office Address: BOX 744, GREAT BEND, KANSAS

Character of Well (Completed as Oil, Gas or Dry Hole)

Date, well completed.....11-23.....1934

Application for plugging filed.....11-25.....1934

Application for plugging approved.....11-25.....1934

Plugging Commenced.....11-23 1934

Plugging Completed..... 11-23 1940

Reason for abandonment of well or producing formation.....DRY HOLE

If a producing well is abandoned, date of last production.....193.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well..... **C. T. ALEXANDER**

Producing formation ARBUCKLE DOLOMITE Depth to top 3441 Bottom 3468 Total Depth of Well 3468 Feet.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, fromfeet tofeet for each plug set.

FILLED HOLE WITH HEAVY MUD; SET WOOD PLUG
AT 549 AND PLUGGED BACK TO 534 WITH 15
SACKS OF CEMENT; FILLED SURFACE CASING WITH HEAVY MUD
AND CAPPED WITH 10 SACKS OF CEMENT.

PLUGGING
FILE SF 24-16-114
BOOK PAGE 123 NE 25

11-29-40

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....SHELL OIL CO., INC.

Address c/o W. M. GHOLSON, BOX 744, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, SS.

W. M. GHOLSON

(employee of owner) ~~XXXXXXXXXXXX~~ of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

BOX 744, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN to before me this 25th day of NOVEMBER, 1940

My commission expires.....12-1-40

17-6058

10-38-5M

Notary Public.

Shell, J. L. Homolka #1
NE NE SE 24-16S-11W
Barton County, Kansas

15-009-19253-0000
Casing Record

8 5/8" cem. 549 with 175 sax cement
& 4 sax Aquagel.

0 - 162 sand, shale & shells
200 shale & shells
220 sand
392 shale, pyrite &
streaks sand
525 sand, shale &
pyrite streaks
708 red rock
748 anhydrite
1150 shale & shells
1289 salt
1400 shale & salt
1533 anhydrite & shale
1580 anhydrite
1660 shale
1758 anhydrite, shale
& lime
1778 lime broken
1814 lime
1912 lime & chert
1962 lime
2087 shale, lime &
chert streaks
2160 lime, shale & chert
2270 shale & lime shells
2355 shale & shells
2681 shale & lime
2709 lime
2709=2707 SLMeasure
Top Topeka 2693
3220 lime
3265 lime & chert
Top Lansing Kansas City 3071
3327 lime
3352 lime & shale
3365 lime
3368 shale
Top Sooy Conglomerate 3365
3370 sand
3375 conglomerate (sand, chert
& lime), mottled shale & lime
3376 sand
3425 shale conglomerate
3441 shale
Top Arbuckle 3441
3468 dolomite T.D.

