

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

Black-Marshall Oil completion
 date 5-9-47
 API NUMBER NA 15-009-03043-
 0080

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, KS. 67530

PHONE#(316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well oil

(Oil, Gas, P&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-14-93 (date)

by Bruce Basye (KCC District Agent's Name)

Is ACD-1 filled? no If not, is well log attached? no not available

Producing Formation ar buckle Depth to Top 3260 Bottom T.D. 3265'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	240	8 5/8"	240'	none
production		0	3261	5 1/2"	3261'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Perforate @ 450', 720' & 1450'. Ran tubing to 2650' run 25 sx. 50/50 Pozmix, 3% CC, pull to 1600' run 25 sx. 50/50 Poz 3% CC, pull to 650' run 150 sx. 50/50 Poz 3% CC. Did not circulate cement, went in with wire line tagged cement @ 1200' Ran 20 sx gel & 50 sx. 60/48 poz. (see back of page. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Saturn Well Service, Inc. License No. 3641

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon. The same are true and correct, so help me God.


(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend, KS 67530

SUBSCRIBED AND SHORN TO before me this 23rd day of September, 19 93

Bessie M. Dewell
 Notary Public
 BE RECEIVED
 Bessie M. Dewell
 COMMISSION

My Commission Expires: 5-20-97



SEP 24 1993 Form 0-11500 05-8

CONSERVATION DIVISION
 Wichita, Kansas

continuation of plugging procedure

Permanent plug @ 750'. Ran 50 sx. 60/40 Poz. 4 1/2 - 5 1/2 annulas pumped 6 sx.
40/60 pozmix 8% gel. 8 5/8" - 5 1/2 annular space pressured up pump no cement
50# pressure. Plug down 3:30 P.M. September 14, 1993

10/15/93
10/15/93
10/15/93