


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas



Locate well correctly on above
Section Plat

Barton County, Sec. 18 Twp. 16S Rge. 11 (W)
Location as "NE/CNW/SW" or footage from lines CSE NW
Lease Owner Gt. Bend Pipe & Supply Company
Lease Name Krier Well No. 3
Office Address Box 414; Gt. Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-4-42 19__
Application for plugging filed 3-9-56 19__
Application for plugging approved 3-12-56 19__
Plugging commenced 3-20-56 19__
Plugging completed 4-6-56 19__
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Topeka Depth to top 2670 Bottom _____ Total Depth of Well 3311 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250'	None
				5 1/2	3291'	1984'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock from 3311 to 3285 dumped 5 sax cement @ 3285' with dump bailer. Top of cement, 3250'. Filled hole with mud to 250', set rock bridge, dumped 20 sax cement. Top of cement 195'. Filled hole with mud to 35', set rock bridge, dumped 10 sax cement for cap.

Name of Plugging Contractor Miller Casing Pulling Company (If additional description is necessary, use BACK of this sheet)
Address Box 711; Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. Nathan Meltzer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Nathan Meltzer

Box 414; Gt. Bend, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 10th day of April, 19 56

My commission expires 3-30-57

Gene Meltzer
Notary Public.

PLUGGING
FILE SEC 18 T 16 R 11W
BOOK PAGE 44 LINE 24

04-13-56


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

BLACK-MARSHALL OIL CO.
Krier No. 3.

SEC. 18 T. 16 R. 11 W
GSE NW

Total Depth. 3311'
Comm. 11-8-42 Comp. 12-4-42
Shot or Treated.
Contractor.
Issued. 1-23-43

County, Barton



CASING:
8 5/8" 250' Cem.
5 1/2" 3291' Cem.

Elevation.

Production. Pot. 3477 B.

Figures Indicate Bottom of Formations.

surface clay	0-40
shale & shells	200
sand	218
lime & shale	250
shale, sand, shells, red bed	510
shale, shells, strks of sand	725
anhydrite	757
shale & red bed	775
red bed, shale, shells	1020
shale & shells-little pyrite	1155
shale & strks salt	1400
lime & shale	1605
shale & lime shells	1730
shale & shells	1745
lime sdy	1770
sand	1779
sdv lime & shale	1820
lime	1870
lime & shale	2062
lime brkn	2180
lime & shale	2353
lime brkn	2440
lime & shale	2660
shale	2670
lime	2694
lime sft	2705
lime	2718
lime-little chert	2755
lime	2854
lime sft	2858
lime	2955
sand	2966
shale sdy	2974
shale	3018
lime K. C.	3059
lime	3082
lime hd	3110
lime sft	3120
lime	3177
lime hd	3196
lime sft	3203
lime hd	3217
lime	3311

Total Dept h.

Top Topeka 2670

RECORDED
STATE OF KANSAS

CONSERVATION

WICHITA

PLUGGING
PER SEC 18 T. 16 R. 11 W
BOOK PAGE 44 LINE 24