


15-009-06353-0000

Give All Information Completely
By the Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Barton County County. Sec. 18 Twp 16 Rge. 11 (E) (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines. SE SE NW
Lease Owner. Black-Marshall Oil Co
Lease Name. Krier Well No. 6
Office Address. Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole). dry-hole
Date well completed. Aug. 25 1946
Application for plugging filed. 8-26-46 19
Application for plugging approved. 9-6-46 19
Plugging commenced. 9-9- 19.6
Plugging completed. 9-13- 19.6
Reason for abandonment of well or producing formation. dry-hole

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. W.H. Kerr
Producing formation. Depth to top. Bottom. Total Depth of Well. 3326' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
			287'	8 5/8"	290'92	none cemented w/90 sks. cement returned.
			3310'	5 1/2"	3320'8"	2545'5"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3326' run 5 sacks cement & 2 sks calseal. Plug back T.D. 3326' to 3280' perf. 3182' to 3186' run 5 sack cement & 2 sks calseal. Plug back 3167' ran 5 sacks cement & 1 sks calseal, perf. 3095'-3103'. Plug back 3010' run 5 sacks cement & 2 sks calseal, perf 2836'-2842'. Run rock to 2750' run 5 sacks cement filled hole with heavy mud to 250', set plug cemented with 15 sks cement mudded to 25' set plug @ 25' & cemented with 10 sacks cement to surface.

PLUGGING
FILE NO. 18 16-120
BOOK PAGE 69 IN. 11



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: Black-Marshall Oil Co.
Address: Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
Walter C. Roberts (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter C Roberts

Clafflin, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of September, 1946.

Wm. Reinhardt Lester
Notary Public.

My commission expires February 19, 1949.

COMPANY: Black-Marshall Oil Co.
CONTRACTOR: Black-Marshall Oil Co.

FAHM: Krier #6
LOCATION: SE SE NE 18-10-11
Barton Co., Kansas

COMMENCED: 7-29-46
COMPLETED: 8-25-46

CASING RECORD:
8 5/8" at 287 - 90 sacks
5 1/2" at 3505 - 175 "

ELEVATION: 1653

PRODUCTION: D & A

<u>Formation</u>	<u>Depth</u>	<u>Tops</u>
Cellar	287	
Shale and sand	520	
Shale and red bed	610	Anhydrite 720
Red bed	720	Topoka 2650
Anhydrite	750	Lansing 3010
Shale	800	Conglomerate 3280
Shale and shells	1253	Arbuckle 3305-10
Shale and salt	1400	
Shale and lime	1465	
Shale and shells	1555	
Shale	1690	
Shale and lime	1760	
Lime	2035	
Shale	2190	
Shale, shells and lime	2369	
Shale	2650	
Shale and lime	2720	
Lime	2960	
Shale	3058	
Lime	3191	
Shale and lime	3208	
Shale	3275	
Lime	3310	
Rotary Total Depth	3310	
Lime and shale	3312	
Lime (dark and soft)	3316	
Lime (white and hard)	3318	
Lime (white and soft)	3322	
Lime (sandy)	3326	
CABLE TOTAL DEPTH	3326	

Shows of Oil


Good SO	2845-50
Slight SO	3099-3106
Fair SO	3185-93

Acidized 500 gallons
" 1000 "

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

BLACK-MARSHALL OIL COMPANY



BY John J. Hark
Assistant Secretary-Treasurer

Subscribed and sworn to before me this 27th day of August, 1946.

Carmen Reinhardt Seibel
Notary Public

My commission expires February 16, 1949.

