


Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-009 - 06765-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 18 Twp. 16S Rge. 11W (E) (W)

Location as "NE/CNWSW" or footage from lines CN/2 SW SE
Lease Owner Brunson Drilling Co., Inc.
Lease Name Redetzke SWD Well No. 7
Office Address 333 First Nat'l. Bank - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) SWD
Date well completed January 25 1953
Application for plugging filed September 15 1955
Application for plugging approved September 16 1955
Plugging commenced September 15 1955
Plugging completed September 17 1955
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3466 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	327'	None
				7" OD	3400'	1155'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with heavy mud from 3466' to 275', set a 10' rock bridge and ran 20 sacks of cement at 265'. Mudded the hole to 25', set a rock bridge and ran 10 sacks of cement on top. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1955 09-29-55

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgewick, ss.
Ralph B. McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1955

My commission expires December 31, 1958
Nanna L. Biley Notary Public.

PLUGGING
FILE REC 18 T 16 R 11W
BOOK PAGE 160 LINE 22

SEP 27 1955 09-27-55
BRUNSON-DRILLING CO., INC.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- BRUNSON DRILLING CO., INC.
Farm-Redetzke No. 7

SEC. 18 T. 16 R. 11W
C N/2 SW SE

Total Depth. 3466
Comm. 1-12-53 Comp. 1-25-53
Shot or Treated.
Contractor. Pam-Kar Drilling Co.
Issued. 2-21-53

County Barton
KANSAS



Elevation. 1887 K.B.

Production. SWDW

CASING:

10 3/4 327'

Figures Indicate Bottom of Formations.

surface soil & clay	20
rock & shale	45
sand & shale	110
shale & shells	285
sand & shale	298
shale & shells	435
shale, shells & sand	550
red bed & sand	715
chalk	721
anhydrite	735
shale & red bed	805
shale & shells	1085
salt & shale	1195
shale & shells	1430
shale & lime	1450
broken lime	1840
shale & shells	1890
shale & lime	1950
shale & shells	2225
shale	2390
shale & shells	2623
shale	2715
lime & shale	3334
lime	3357
lime & shale	3366
lime, shale & pyrite	3401
Arbuckle lime	3408
sand	3414
lime, shale & chert	3466
Total Depth	

TOPS:

Heebner	2940
Toronto	2959
Brown lime	3035
Lansing	3055
Conglomerate	3329
Arbuckle	3355

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1955

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18 T 16 R 11W
BOOK PAGE 150 LINE 20