


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-009-07127-0000  
WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Barton County. Sec. 18 Twp. 16 Rge. 11 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SW SW  
Lease Owner National Cooperative Refinery Association  
Lease Name A. Hoffman "C" Well No. 3  
Office Address 305 Rule Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 18, 1950  
Application for plugging filed August 15, 1956  
Application for plugging approved August 16, 1956  
Plugging commenced August 25, 1956  
Plugging completed August 30, 1956  
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production July 1, 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3321 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308'	None-cemented
				5 1/2"	3320'	2754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3321' to 3310' and dumped 5 sacks of cement from 3310' to 3225'. Pulled 5 1/2" casing. Filled hole with mud from 3225' to 300'. Set rock bridge from 300' to 295'. Mixed and dumped 20 sacks of cement from 295' to 245'. Filled up with mud from 245' to 35', set rock bridge from 35' to 30'. Mixed and poured 10 sacks of cement from 30' to top of surface casing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company  
Address Box 304, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. R. Sears (employee of owner) or (~~owner~~/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of September, 19 56

My commission expires November 26, 1956.

Nell McComb Notary Public.

PLUGGING  
FILE SEC. 18 T. 16 R. 11W  
BOOK PAGE 90 LINE 31

09-07-56

WELL LOG

Company NCRA et. al  
Tools Flournoy & Williams

A. Hoffman C #3  
SE SW SW  
Sec. 18-16-11W  
Barton County, Kansas

Commenced 11-4-50  
Completed 11-14-50

Casing 8 5/8" 308'  
5 1/2" 3320'

<u>Formation</u>	<u>Depth</u>
Post Rock	60
Shale & Shells	308
Redbed & Shale Sand	756
Anhydrite	770
Redbed & Shale	1160
Salt & Shale	1320
Shale & Shells	1460
Shale & Lime	1670
Shale & Lime Shells	1815
Sandy Lime & Shale	1940
Lime & Shale	2065
Shale & Shells	2150
Lime & Shale	2230
Shale & Lime Shells	2400
Lime & Shale	2745
Lime	2980
Shale & Lime	3060
Lime	3320
Arbuckle	3321 T.D.

<u>Tops</u>	
Heebner	2947
Toronto	2965
Brown Lime	3037
Lansing	3057
Arbuckle	3319
Total Depth	3321

CERTIFICATION

I, Chester Williams, certify that the above is a true and correct copy of the driller's log of the above well.

*Chester Williams*

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1950

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 18 T 16 R 11W  
BOOK PAGE 90 LINE 31