


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-009-07125-0000
WELL PLUGGING RECORD

Barton County, Sec. 18 Twp. 16S Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW
Lease Owner National Cooperative Refinery Association
Lease Name A. HOFFMAN "B" Well No. 4
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 1950
Application for plugging filed June 28, 1961
Application for plugging approved June 29, 1961
Plugging commenced July 19, 1961
Plugging completed July 26, 1961
Reason for abandonment of well or producing formation Depletion



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production November 1, 1960
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bilbert Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	279'	None
				5-1/2"	3322'	2531'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3302 feet to 2940 feet. Mixed and dumped 4 sacks of cement from 2940 feet to 2908 feet. Pulled 2531.30 feet of 5 1/2" casing. Mudded hole to 280 feet, set 10 foot rock bridge to 270 feet. Dumped 20 sacks of cement to 210 feet. Mudded hole to 40 feet, set 10 foot rock bridge to 30 feet. Dumped 10 sacks of cement on up to base of cellar.

8-14-61

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Ace Pipe Pulling Company
Address Box 304, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (~~owner/operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1961
Nell McComb

My commission expires November 26, 1964
Nell McComb Notary Public.

WELL LOG

Company - NCRA
Contractor - Flourney & Williams
Commenced - 12-28-49
Completed - 1-7-50

Hoffman "B" #4
SW ND SW
Sec. 18-16S-11W
Barton County, Kansas

Casing - 279' 8-5/8"
3322' 5-1/2"

Surface	15
Rock	25
Shale and shells	70
Sand and shale	85
Shale and shells	217
Sand, shale and shells	279
Shale and shells	360
Sand and shale	410
Shale, Red Bed, shells	754
Anhydrite	779
Shale and shells	1185
Red Bed and sand	1430
Salt and shale	1470
Shale and shells	1720
Lime and shale	2680
Broken Lime	2715
Lime	2835
Lime and shale	2910
Lime	3325

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Chester Williams of lawful age being first duly sworn depose and state that the above formations and depths are true and correct as taken from the daily drilling report of the Hoffman "B" #4 well in the SW NE SW 18-16S-11W, Barton County, Kansas.

Chester Williams

Subscribed and sworn to before me this 16th day of January, 1950.

Rola Buss
Notary Public

My commission expires Nov. 3, 1952