

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-009-15185-0001  
API NUMBER N/A

LEASE NAME Schartz

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 18 TWP. 16 RGE. 11W ~~XX~~ or (W)

COUNTY Barton

Date Well Completed 7-1955

Plugging Commenced         

Plugging Completed 9-24-92

WICHITA, KANSAS  
CONSERVATION DIVISION

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2661 SEP 30 1992 9-30-92

LEASE OPERATOR Kahan & Associates, Inc.

ADDRESS P.O. Box 559 Tulsa, Oklahoma 74101

PHONE# (918) 587-4159 OPERATORS LICENSE NO. 4252

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3474'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				12"	196'	none
				8 5/8"	2820'	none
				7"	3293'	none
				5 1/2"	3326'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Mixed approx. 50 sacks 60/40 8% gel with 100# hulls down 12" casing MAX Pressure 400#, Shut In @300#, Mixed approx 40 sacks 60/40 8% gel with 100# hulls down 8 5/8" casing, Max Pressure 700#, Shut In 500#, Mixed Approx. 230 sacks 60/40 8% gel with 250# hulls down 5" casing, Max Pressure 1700#, Shut In @700#.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kahan & Associates, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelsö (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelsö

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 28 day of September, 19 92

Irene Herzberg  
Notary Public

My Commission Expires:         

