


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-009-19261-0001
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County. Sec. 18 Twp. 16 Rge. 11 ~~03~~ XX (W)

Location as "NE/CNW*SW*" or footage from lines C NL, S 1/2 NE
Lease Owner Solar Oil Company
Lease Name K. Schartz Well No. 13
Office Address 1117 Union Nat'l. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed Feb. 16, 19 53
Application for plugging filed Nov. 25, 19 57
Application for plugging approved Nov. 26, 19 57
Plugging commenced Nov. 26, 19 57
Plugging completed Dec. 4, 19 57
Reason for abandonment of well or producing formation Oil depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production April 22, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truen
Producing formation Kansas City Depth to top 3010 Bottom 3216 Total Depth of Well 3355 Feet
Show depth and thickness of all water, oil and gas formations. plugged to 3200'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	708.68	none
				5 1/2"	334.8	2767.95

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand to 3170' and dump 5 sacks cement. Pull 5 1/2" casing. Mud to 300' and set 5' rock bridge and dump 25 sacks cement. Mud to 35' and set 5' rock bridge and dump 10 sacks cement to base of cellar.

JAN 31 1958 01-31-58

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James Davis, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis, Jr.
1117 Union National Bldg., Wichita, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of January, 19 58

Leota Lee Miller
Leota Lee Miller Notary Public.

My commission expires July 27, 1959

PLUGGING
FILE SEC 18 T. 16 R. 116
BOOK PAGE 63 LINE 40

SCHARTZ #13

C NL S/2 NE/4 of Section 18-16S-11W Barton County, Kansas

Rigged up Rotary Tools 2/4/53
Tore Down Rotary Tools 2/18/53

Run 24 Jts (711') of 8 5/8" 8 RD. Thd Surface Pipe set at 711'. Cemented with 300 sacks of cement.
Run 105 Jts. (3358') of 5 1/2" 8 Rd Thd Casing, set @ 3352'. Cemented with 100 sacks cement.

ELEVATION - 1870 Rotary Bushing

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Surface soil, shale & rock	0'	96'	
Shale & shells	96	260	
Shale & sand streaks	260	390	
Shale & shells	390	530	TOPS:
Redbed, shale	530	680	
Redbed	680	702	Tarkio 2398
Anhydrite	702	730	Topeka 2655
Shale & shells	730	1315	Heebner 2898
Shale	1315	1603	Douglas 2944
Lime & shale	1603	1700	Brown Lime 2993
Lime	1700	1770	Lansing KC 3010
Lime & shale streaks	1770	1865	Base KC 3216
Lime	1865	1970	Congl. 3288
Lime & shale streaks	1970	2123	Arbuckle 3296
Shale	2123	2515	Sandy Phase
Shale & lime streaks	2515	2610	Arbuckle 3336
Shale & lime	2610	2786	
Lime	2786	2895	
Lime & sand	2895	2956	
Lime & shale	2956	3031	
Lime & shale streaks	3031	3134	
Lime	3134	3314	
Lime, sand & lime	3314	3347	
Lime	3347	3355	TD

I, June Swaney, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

June Swaney

Subscribed and sworn to before me this 20th day of February, 1953.

Warren H. Fobke

My commission expires: September 24, 1955

RECEIVED
CONSERVATION COMMISSION

NOV 26 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18 T 16 R 11 W
BOOK PAGE 63 LINE 40

Ace Pipe Pulling Co.

License No. 2

Telephone 3602

Box 304

GREAT BEND, KANSAS

PLUGGING RECORD

Moved In 11-26-57

Completed 12-4-57

Company Solar Oil Co.

Address _____

Lease Schartz

Well No. 13 Cy. Barton

State Ks.

Legal Description CN S $\frac{1}{2}$ NE

Sec. 18 Twp. 16 Rng. 11w

Total Depth 3355'

Size Pipe 5 $\frac{1}{2}$

Weight 17

Casing Cemented At 3348'

With 100'

Sacks

Size Surface Pipe 8 5/8

Cemented At 709'

With circ.

Sacks

Other Strings _____

Well Plugged Back To 3200'

Top Perforations 3182 $\frac{1}{2}$ -88 $\frac{1}{2}$ '

Plugging Orders Plug back with sand to 3170' and dump 5 sx. cement. Pull 5 $\frac{1}{2}$

casing. Mud to 300' and set 5' rock bridge and dump 25 sx. cement

Mud to 35' and set 5' rock bridge and dump 10 sx. cement to base

of cellar.

State Supervisor Don Truen

Phone 2046 Gorham, Ks.

Company Representative Bob McFarland

Phone GL-3-6044 Great Bend, Ks.

RECEIVED

STATE CORPORATE COMMISSION

DEC 14 1957

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 18 T 16 R 11w
BOOK PAGE 63 LINE 40

66-3-1301