


WELL PLUGGING RECORD

15-009-19257-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County, Sec. 18 Twp. 16 Rge. 11 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE SE NE
Lease Owner Solar Oil Company
Lease Name K. Schartz Well No. 11
Office Address 1117 Union National Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed Jan. 13, 19.52
Application for plugging filed Oct. 6, 19.58
Application for plugging approved Oct. 7, 19.58
Plugging commenced Oct. 10, 19.58
Plugging completed Oct. 11, 19.58
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production Sept. 30, 19.58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truen, Gorham, Kansas
Producing formation Arbuckle Depth to top 3301 Bottom 3311 Total Depth of Well 3311 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	713.22	none
				5 1/2"	3303'	2760'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug back with sand to 3290'. Dump 5 sacks cement. Cement 3290 to 3250'.
Mud to 350'. Set 10' rock bridge from 350' to 340'. Dump 25 sacks cement.
Cement to 265'. Mud from 265' to 40'. Set 10' rock bridge from 40' to
30'. Dump 10 sacks cement from 30' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pine Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
James Davis, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well has filed and that the same are true and correct. So help me God.

10-18-58 (Signature) James Davis, Jr.
1117 Union National Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 16th day of October, 1958

My commission expires July 27, 1959
Leota Lee Miller Notary Public

PLUGGING
FILE SEC. 18 T. 16 R. 11W
BOOK PAGE 134 LINE 13

SOLAR OIL CORPORATION

ELEVATION - 1877 DF
1879 KB

K. Schartz #11

NE SE NE 18-16-11W., Barton County, Kansas

CONTRACTOR * BRADEN DRILLING

Commenced: 12/4/51
Completed 12/13/51

Production - 20 bbls. oil

Figures indicate bottoms of formations

shale and shells	704	
Anhydrite	714	Set 713.22' 8 5/8" 32# Seamless casing cemented with 325 sacks Lehigh cement
Anhydrite	730	
shale and shells	1440	
shells and sand	1600	
shale	1710	
lime and shale	2235	
shale	2475	
shale and lime	2760	
lime	3307	Set 3299' 5 1/2" 17# casing @ 3303' K.B. cemented with 100 sacks Lehigh cement
TOTAL DEPTH w/Cable tools	3311	

TOPS: Anhydrite	704'
Topeka	2685'
Heebner	2912
Brown Lime	3004
Lansing K.C.	3025
Arbuckle	3301

MAR 25 1952

RECEIVED
STAT
OCT 7 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE	SEC. 18 T. 16 R. 11W
BOOK	PAGE 134 LINE 13