

Form CP-3  
Rev. 6-26-62

 KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas 67202

Lease Name R.L. Becker Well No. 1

Location SE NE SE Sec. 29 Twp. 22 Rge. 33 (~~22~~) (W)

County Finney Total Depth 4794' 4825'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 300PM Day 19 Month 3 Year 1968

The Above well was plugged as follows:

8 5/8" to 387' circulated w/ cement. 4 1/2" to 4825' cemented.

Top Perforations 4730' Plug bottom w/ 15 sacks cement.

Top of cement 4600' Mud 4600' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 380'

Spotted 35 sacks cement 380' to 280' Mud 280' to 45'

Plug. Hulls & 15 sacks cement 45' to 0' Company Pump

Pulled 1495' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/21/68INV. NO. 7457-WSigned: Edmund J. Egan

Well Plugging Supervisor