

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Lonita Oil Corp.Inc.

Complete Address: 704 Bitting Bldg. Wichita, Kansas

Lease Name Damme Well No. A-3

Location SW NW SW Sec. 33 Twp. 22S Rge. 33 (E) (W)

County Finney Total Depth 4920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Lonita Oil Corp.Inc.

Address: Wichita, Kansas License No.

Operation Completed: Hour 730AM Day 20 Month 11 Year 63

The Above well was plugged as follows:

8 5/8"-386' Circulated w/cement.

Mud 4920' to 2700' - Spotted 110 Sax.cement at 2700' to 2370'

Mud 2370' to 700' Snotted 25 Sax.cement 700' to 625'

Mud 625' to 385' Spotted 25 Sax.cement 385' to 310'

Mud 310' to 40' Plug,Hulls,15 Sax.cement 40' to 0

Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. P. Roberts*
Well Plugging Supervisor

DATE 11/27/63

INV. NO. 8175-W