

*46*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thor Corporation

Complete Address: Box 897 Great Bend, Kansas

Lease Name Rooney Well No. 1

Location C NW NW Sec. 4 Twp. 22 Rge. 35 (E) (W)

County Kearny Total Depth 5085'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 8 PM Day 24 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" - 823' Circulated w/cement. 4 1/2" - 4599' Cemented.

Perforations 4463' to 4505'

Sand hole from bottom to 4450' 10 Sax. cement 4450' to 4350'

Mud 4350' to 800' 35 Sax. cement 800' to 700'

Mud 700' to 50' Rock bridge 50' to 40'

15 Sax. cement 40' to 0 Weld cap on surface. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Sheph Scott*  
Well Plugging Supervisor

DATE 10/28/63  
INV. NO. 4959-U