

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-009-21660-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Brougher Oil Inc.

Complete Address P.O. Drawer 1767, Great Bend, Ks. 67530

Lease Name Baummeister Well No. 9

Location SW NE SW Sec. 23 Twp. 16 Rge. 11 (East) (West)

County Barton Total Depth 3393'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. _____

Operation Completed: Hour: 5:00 PM Day: 10 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 249' S.P. cas. w/ 200 sacks common. 5 1/2" set at 3348' w/ 150 sacks common.
Top perf. at 2962'. Plugged hole w/ sand & 5 sacks cement to 2900'. Shot pipe 2 times
& recovered 2325'. Ordered 140 sacks 50 permits 4 3/8" gel. 3 3/8" gel. 5 sacks hulls,
20 sacks gel., & 8 5/8" plug. Pumped into S.P., 4 sacks hulls, 16 sacks gel., 70 sacks cement,
4 sacks gel., 1 sack hulls, released plug & followed w/ 70 sacks cement.

Maximum pressure ~~1000~~ 1000 pounds.

Amount of Surface Casing: 249' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Gilbert R. Schuch
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
AUG 23 1982
8-23-82
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 8-30-82

INV. NO. 982 W