

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 095-30083-0000 (of this well)

Operator's Full Name Brougber Oil, Inc.

Complete Address P. O. Box 1367, Great Bend, Kansas 67530

Lease Name Burmeister Well No. 1

Location SE <sup>NW</sup> SW Sec. 23 Twp. 16 Rge. 11 XX (W) X

County Barton Total Depth 3377'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 10:15 AM Day 16 Month 4 Year 1980

The above well was plugged as follows:

Sanded back to 3200' and 5 sx cement with dump bailer.

Squeezed thru 3 5/8" surface casing with 4 sx hulls,

25 sx mud gel, 2 sx hulls, and 100 sx cement.

Max. pres 800#. Shut in pres. 200#.

Recovered 2211' of 5 1/2" casing.

Plugged back to 3280'. Top perforation at 3246'.

3370' of 5 1/2" casing cemented with 100 sx cement.

225' of 3 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 4-18-80

INV. NO. 1954W

Signed: Duane J. Rankin  
Well Plugging Supervisor

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1980  
CONSERVATION DIVISION  
Wichita, Kansas