

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-055-00317-0000

API NUMBER Completed 9-9-55

LEASE NAME Niquette

WELL NUMBER 1

3340 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 13 TWP. 22 RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 9-9-55

Plugging Commenced 11-1-93

Plugging Completed 11-1-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-1-93 (date)

by Steve Middleton - Dodge City (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Hugoton Chase Depth to Top 2555 Bottom 2611 T.D. 2611

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Hugoton-Chase	Gas	2520	2611	10-3/4"	284	0
				7"	2600	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each section. Rig HLS. Set 7" CIBP @ 2457'. Dump bail 2 sks cement on top of CIBP. Load 7" casing w/ water. Perforate 7" casing from 1104'-1100' w/ 4 JSPE. Mix and pump 425 sks 65/35 Poz "C" w/ 281 sks down 7" casing at maximum pressure of 590 psi. Steve Middleton w/ KCC was concerned about breaking down formations w/ the pressure and ask for the remaining 144 sks cement to be pumped (if additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Dowell - Schlumberger License No. \_\_\_\_\_

Address Ulysses, KS 11-4-93

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc. RECEIVED

STATE OF Kansas COUNTY OF Finney, ss.

Ken Jehlik (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well, and that the statements and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Ken Jehlik AC

(Address) P.O. Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 93

Judy Richmeier  
Notary Public

My Commission Expires: August 15, 1996

down the 10-3/4" X 7" casing annulus. Maximum pressure down annulus was 330 psi. Shut-in pressure = 80 psi. Cut off casing 3' below ground level. Weld on plate. Backfill hole and recontour location.