

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-055-21,018-0000

LEASE NAME Boyd "A"

WELL NUMBER 1-16

4950 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 22 RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 8-8-91

Plugging Commenced 8-9-91

Plugging Completed 8-9-91

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, Ks 67202

PHONE# (316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-8-91 (date)

by Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD | STATE CORP. RECORD

9-10-91  
 RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
		0	1896'	8-5/8"	1896'	None
						SFP 10 1001
						CO.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plug and abandon using 60-40 Pozmix, 6% gel. Set 1st plug @ 2800' w/80 sks, 2nd plug @ 2000' w/ 50 sks, 3rd plug @ 1000' w/50 sks, 4th plug @ 600' w/50 sks, plug from 40' to surface with 10 sks; 10 sacks in mousehole and 15 sacks in rathole. Plugging complete 8-8-91.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beredco Inc. License No. 5147

Address 401 E. Douglas, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 110 S. Main, Suite 500  
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14 day of August, 19 91

Deborah Ann Paulus  
 Notary Public

