


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kearny County, Sec. 4 Twp. 22S Rge. 35WE/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SW SW

Lease Owner ZENITH DRILLING CORPORATION, INC.  
Lease Name Rooney 'B' Well No. 1  
Office Address 200 W. Douglas, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed 7-5-1976  
Application for plugging filed 7-5-1976  
Application for plugging approved 7-5-1976  
Plugging commenced 7-5-1976  
Plugging completed 7-5-1976

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4965  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf.	249	8-5/8"	2241	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED  
STATE CORPORATION COMMISSION

Fluid to 720', plug, 70 sx cement, UL 16 1976  
Fluid to 240', plug, 20 sx cement, 7-16-76  
Fluid to 40', plug, 10 sx cement.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor D N B DRILLING, INC.  
701 First National Building  
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF \_\_\_\_\_, ss.  
JAMES L. DONELSON (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson  
701 First National Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 76

Ella Priess

Notary Public.

My commission expires 8-25-76

Ella Priess

Ella Priess  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

ZENITH DRILLING CORPORATION, INC.  
No 1 Rooney 'B'  
SW SW, Sec. 4-228-35W  
Kearny County, Kansas

Elev: 3103 K.B.

Commenced: 6-23-76  
Completed: 7-5-76

Surface Casing: 241' of  
8-5/8" cemented w/300 sx  
common cement, 2% Gel, 3% cc.

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 249
Sand & Shale	249 - 725
Shale & Red Bed	725 - 1392
Sand, Shale & Shells	1392 - 2165
Shale	2165 - 2469
Shale & Lime	2469 - 2665
Lime & Shale w/Sand Strks	2665 - 2955
Lime & Shale	2955 - 3975
Lime & Shale w/ Sand Streaks	3975 - 4215
Lime & Shale	4215 - 4345
Lime	4345 - 4915
Lime & Chert	4915 - 4965 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 15th day of July, 1976.

RECEIVED  
REGISTRATION  
JUL 16 1976  
REGISTRATION DIVISION  
Topeka, Kansas

*Ella Priess*  
Ella Priess, Notary Public

*Ella Priess*  
STATE NOTARY PUBLIC  
Sedgwick County, Kansas  
My Com. Expires Aug. 25, 1978