


15-009-00565-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 23 Twp. 16 Rge. 11 (E) W.(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE NE
Lease Owner B & R Drilling, Inc.
Lease Name Breford "B" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 18, 1950 19
Application for plugging filed January 10, 1951 Verbally 19
Application for plugging approved January 10, 1951 Verbally 19
Plugging commenced January 18, 1951 19
Plugging completed January 23, 1951 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3375' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	182'	None
				5 1/2"	3372'	2052'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Record

Mudded to 170' set 10' rock bridge at 170'
and dumped 15 sacks of cement at 160' mudded hole
to 30' set 10' rock bridge at 30' and dumped 10
sacks of cement filled hole to top.

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 1951

My commission expires 6-17-54

Notary Public.

28-5091-8 8-30-10M
PLUGGING
FILE SEC 23-16-R-110
BOOK PAGE 54 LINE 29

B & R Drilling, Inc.
Breford "B" #1

15-009-00565-0000
SE SE NE Sec. 23-16S-11W
Barton County, Kansas

Total Depth: 3375' RTD
Comm: 11-6-50
Comp: 11-18-50

Casing

8 5/8" Set @ 182'
5 1/2" Set @ 3372'

Cement

125 Sacks of Monarch
100 Sacks of Monarch

Formation

Depth:

Shale-Shells-Sand	182
Shale	272
Sand	330
Shale-Shells	500
Sand-Ron	520
Shale	546
Sand-	590
Shale-Lime	740
Shale-Shells	810
Shale-Sand	895
Sand Shale-Red	950
Shale-Shells-Redbed	1000
Shale-Shells	1175
Salt-Shale	1400
Shale-Shells	1405
Shale-Shells	1436
Anhydrite	1514
Lime-Shale	1695
Fort Riley	1820
Lime-Shale	2240
Sandy Lime-Shale	2400
Lime-Shale	2840
Topeka Lime	2870
Lime	2975
Lime-Shale	3025
Shale-Lime	3062
Brown Lime	3080
Lansing K. C. Lime	3095
Lime	3375 RTD
Arbuckle Dolo.	3400


STATE OF KANSAS)
)SS
RUSSELL COUNTY)

RECEIVED
CORPORATION COMMISSION
JAN 11 1951
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true
and correct to the best of my knowledge.

Violet Keller

Subscribed and sworn to before me this 29th day of November, 1950.



PLUGGING
FILE SEC-23-16S-11W
BOOK PAGE 54 LINE 29

Clara Sumner
Notary Public

My commission expires: 1-17-54

15-009-00565-0000

B. & R Drilling, Inc.
Breford "B" # 1

SE SE NE Sec. 23-16S-11W
Barton County, Kansas

Total Depth: 3375'
Comm: 11-6-50
Comp: 11-18-50

Casing

Cement

8 5/8" Set @ 182'
5 1/2" Set @ 3372'

125 Sacks Of Monarch
100 Sacks of Monarch

Formation	Depth:
Shale-Shells-Sand	182
Shale	272
Sand	330
Shale-Shells	500
Sand-Iron	520
Shale	546
Sand-	590
Shale-Lime	740
Shale-Shells	810
Shale-Sand	895
Sand Shale-Red	950
Shale-Shells-Redbed	1000
Shale-Shells	1175
Salt-Shale	1400
Shale-Shells	1405
Shale-Shells	1436
Anhydrite	1514
Lime-Shale	1695
Fort Riley	1820
Lime-Shale	2240
Sandy Lime-Shale	2400
Lime-Shale	2840
Topeka Lime	2870
Lime	2975
Lime-Shale	3025
Shale-Lime	3062
Brown Lime	3080
Lansing K. C. Lime	3095
Lime	3375

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1951
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)SS
RUSSELL COUNTY)

I hereby certify that the above information is true
and correct to the best of my knowledge.

Walter L. ...

Subscribed and sworn to before me this 29th day of November, 1950.

PLUGGING
FILE SEC 23-16-11W
BOOK PAGE 54 LINE 29

Walter L. ...
Notary Public

My commission expires: 6-17-54