


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Barton County. Sec. 23 Twp. 16 Rge. 11W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner Bennett & Roberts Oil Operations
Lease Name Frees Well No. 1
Office Address Drawer 633, Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 6/27 1960
Application for plugging filed 2/6 1961
Application for plugging approved 2/8 1961
Plugging commenced 2/10 1961
Plugging completed 2/13 1961
Reason for abandonment of well or producing formation Production too small to
operate economically
If a producing well is abandoned, date of last production 1/27 1961
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan 3381
Producing formation Arbuckle Depth to top _____ Bottom _____ Total Depth of Well 3366 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320'	None
				5 1/2"	3371 1/2'	1702

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made plug back to 3090', ran 5 sx cement. Load casing w/water.
Shot casing at 2559, 2242, 2112, 2021, 1892, 1795, 1700. Pulled
53 jts. Mudded hole to 320', set 10' rock bridge. Mixed and ran 25
sx cement w/dump bailer. Mudded hole to 40', set 10' rock bridge.
Ran 10 sx cement to base of cellar. Cut off braden head.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.

SUBSCRIBED AND SWORN TO before me this 15th day of February, 1961

My commission expires 6/17/62 Notary Public.

15-0091-0-10-26-00-00

Bennett & Roberts Oil Operations
FREES #1

SW SE NE Section 23-16-11W
Barton County, Kansas

RID 3375

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 6/9/60
Completed 6/18/60

Set 8 5/8" @ 320' w/165 sx cement.
Set 5 1/2" @ 337 1/2' w/100 sx cement

Surface Clay	30
Post Rock	40
Shale	65
Sand	75
Shale & Shells	280
Shale	320
Red Bed	380
Shale & Shells	2/10/61 560
Sand	660
Red Bed	730
Anhydrite	755
Shale & Shells	1400
Lime	1470
Lime & Shale	1770
Lime	1895
Lime & Shale	2060
Shale & Shells	2165
Shale & Lime	2845
Lime	2985
Lime & Shale	3089
Lime	3375

STATE CORPORATION DIVISION
 FEB 7 1961
 COMMISSION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS)
RUSSELL COUNTY) SS

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By *James Lee Marshall*

Subscribed and sworn to before me this 20th day of June, 1960

Notary Public

My Commission Expires 6/17/62

