



Locate well correctly on above Section Plat

Barton County. Sec. 23 Twp. 16S Rge. 11 W (E) (W)
 Location as "NE/CNW/SW" or footage from lines SE SW NW
 Lease Owner ALPINE OIL & ROYALTY CO., INC.
 Lease Name Jesse Pichner Well No. 1
 Office Address 800 Bitting Building, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) dry hole
 Date well completed October 13, 1965 19
 Application for plugging filed October 13, 1965 (phone) 19
 Application for plugging approved October 13, 1965 (phone) 19
 Plugging commenced October 13, 1965 (phone) 19
 Plugging completed October 13, 1965 at 7:30 P. M. 19
 Reason for abandonment of well or producing formation non-productive in commercial quantities
 If a producing well is abandoned, date of last production _____ 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3427 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud from total depth, 3427 feet, to 300 feet. Set plug at 300 feet with 25 sacks cement. Second plug at 40 feet with 10 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 14 1965
 10-14-65
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Gabbert-Jones, Inc.
 Address 514 Orpheum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
800 Bitting Building, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1965

My commission expires August 10, 1969

[Signature]
 Virginia Mundell
 Notary Public.

15-009-30273-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1965

JESSE PICHNER #1
SE SW NW SECTION 23-16S-11W
BARTON COUNTY, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

COMMENCED: OCTOBER 4, 1965
COMPLETED: OCTOBER 13, 1965

OPERATOR - ALPINE OIL & ROYALTY Co., INC.

DEPTH	FORMATION	REMARKS
FROM	To	
0	235	SHALE AND SAND
235	305	RED BED
305	720	RED BED AND SHALE
720	750	ANHYDRITE
750	1200	RED ROCK AND SHALE
1200	2805	LIME AND SHALE
2805	3400	LIME
3400	3410	LIME AND CHERT
3410	3427	LIME
3427	TD	DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE SE SW NW SECTION 23-16S-11W, BARTON COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 19TH DAY OF OCTOBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.