


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

*Re*  
**WELL PLUGGING RECORD**



Locate well correctly on above Section Plat

Reno County, Sec. 12 Twp. 23 Rge. 10 (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Cities Service Pet. Co. (Drillers Producers)  
Lease Name Heylman "B" Well No. 4  
Office Address Box 144, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dil  
Date well completed 3-12-61 19  
Application for plugging filed 3-8-61 19  
Application for plugging approved 3-8-61 19  
Plugging commenced 3-8-61 19  
Plugging completed 3-12-61 19  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Fred Hampell  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3748 Feet  
Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sand to 3725' mixed and run 4 sacks cement. Pulled casing. Mudded hole to 240' set 10' rock bridge with 20 sacks cement. Mud to 40' set 10' rock bridge with 10 sacks cement to base of cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 17 1961

CONSERVATION DIVISION  
Wichita, Kansas

3-17-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren G. Horner Pres.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of March, 19 61

My commission expires 24 October 1964

Sidney D. Miller  
Notary Public.



Unitized 4-1-55  
(OI-57676)

15-155-19261-0000

072

Peace Creek Unit Tract #23

J. O. Number B-23205

Lease HELMERICH'S BLDG

Well No. 4

County: RENO

State: KANSAS

Lease No. 928

Description: SW NE NW 12-235-10W

Location: 990' S of 990' W of N/4 Cor. 110

Company Interest:

Operator if Partnership:

Insurance Requested: \$2500.

R-7-29-42  
C-8-20-42

Insurance Cancelled:

8-27-42

Commencement Notice: 7-31-42

Completion Notice:

8-31-42

Drilling Started: 7-29-42

Drilling Completed:

8-27-42

Producing Horizon: Viola Lime

Initial Production: Oil 3000

Water None

Elevation Top 3743

Total Depth 3748

Penetration 5

Casing Record

Size	Wt.	Amt. Set	Amt. Pulled	Left In	Cement
8 5/8"		243'	0	243'	200 sq.
5 1/2"		3745'	0	3745'	75 "

Contractor Helmerich's Payne Inc. Type of Tools REC  
415 Philtower Bldg. Tulsa, Oklahoma Drilling Progress Cash

Contract Rate 2.50  
150.  
90.

1942		Released.
7-24		Location
27		Pits & collar complete
28		Drig rat hole
29		Set 8 5/8" @ 243' / 200 sq
30	243'	W.O.C.S.
31	243'	Drig.
8-3-42	2210'	✓
4	2470'	✓
5	2795'	✓
6	2970'	✓
7	3134'	✓
10	3610'	✓
11	3625'	✓
12	3710'	✓
13	3754'	Top Viola 3743' Intd. 5 1/2" @ 3745' in 75' sand
14,17	3754'	W.O.C.S.
18,19	3754'	W.O. Dily unit
20	3754'	W.O.C.S.
21	3754'	Bailing Mud.
22	3748'	S.L.M.
24	3748'	60' water in 3 hrs. Show oil
25	3748'	Swabbed dry, no oil or water.
26	3748'	Acidized w/ 500 gals. Swabbed well flowed
		4 hrs, 18, 17, 13 & 17 lbs.
27	3748'	Flowing 19 lbs/hr. on test
28	3748'	Prod. 3000 oil, no water, 24 hrs B.H.P. fange

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1961  
CONSERVATION DIVISION  
Wichita, Kansas

make application  
3-6-61  
mail log and  
Application to  
Corps. Comm. Wichita  
Warren Bell  
Homer