

OF KANSAS
CORPORATION COMMISSION
Market, Room 2078
KS 67202

WELL PLUGGING RECORD
K.A.C.R.-62-3-117

15-051-23712-0000

API NUMBER 051-23712

LEASE NAME Dinges

WELL NUMBER #1

4620 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 9 TWP. 15 SRGE. 18 (E) or (W)

COUNTY ELLIS

Date Well Completed 1-1-83

Plugging Commenced 1-13-2000

Plugging Completed 1-17-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

OPERATOR Quality Well Service

5415 E Main, Sterling, KS 67579

(sic) 278-2026 OPERATORS LICENSE NO. 31925

Use of Well oil

(Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 1-13-2000 (date)

Hays KCC (KCC District Agent's Name).

Well filed? yes if not, is well log attached? yes

Geologic Formation ARKWILE Depth to Top 3640 Bottom 3675 T.D. 3680

Depth and thickness of all water, oil and gas formations.

GAS OR WATER RECORD | **CASING RECORD**

Location	Content	From	To	Size	Put In	Pulled out
				8.50"	1215'	
				5.50"	3677'	2700'

In detail the manner in which the well was plugged, indicating where the mud fluid was used and the method or methods used in introducing it into the hole. If cement or other plug used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3,470' Bailed 5 sacks. Shot 2,742'. Pulled pipe to 1,400'. Pumped 130 sacks with 3 huls. Pulled to 1,235'. Dumped 50 sacks with 1 hul. Pulled to 445'. Dumped 75 sacks with 1 hul. Circulated cement to surface. Pulled rest of pipe. Tapped with 1 1/2" sacks. Hole stayed full.

Plugging Contractor Quality Well Service License No. 31925

PARTY RESPONSIBLE FOR PLUGGING FEES: Quality Well Service

COUNTY OF _____, ss.

(Employee of Operator) or (Operator) of described well, being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN TO before me this _____ day of _____, 19____

Notary Public

My Commission Expires: _____



Form 0-1
Revised 05-88

They send in