



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

7-29-59

RECEIVED
 JUL 29 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 7-18, 1959, authorized the following plugging operation:

Operator's Full Name: Kansas-Nebraska Mutual Gas Co Inc

Complete Address: 300 N. St. Joseph, Hastings, Nebraska

Lease Name: Rooney Well No. 4

Location: 200 S 300 W of E Sec. 10 Twp. 12 Rge. 35 (E) (W) X

County: Hearney Total Depth: 2680

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

10 3/4" 298' C.W.C. 7" 2696' C.W.C. Drilled and set to
2719' Prof 2632-64' Comp 6-16-1953 May 1958
P.B. 2668. all perforations shut off. Pipe collapsed
1608' 7-19-59 dumped 5 cu. cut with fader
Mud to 300' set P.B. 8 cu. cut. Mud to 45' Dumped
7 cu. cut to B of Q
New well drilled for replacement

Very truly yours,

Signed: M. R. Pines
 Conservation Division Agent