

15095-007100000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 7 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shallow Water Refining Company

Complete Address: 1325 Wichita Plaza, Wichita, Kansas

Lease Name Bartholomew Unit Tract # 13 Well No. # 1

Location NE SE SE Sec. 36 Twp. 27 Rge. 5 (E) (W) W

County Kingman Total Depth 3790'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Khight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00AM Day 2nd Month Sept. Year 1965

The Above well was plugged as follows:

192' of 8 5/8" surface pipe, cemented with 140 sacks. 3788' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 3775', and cemented with 5 sacks. 3340' of 5 1/2" long string
was recovered from the hole. Hole was filled with mud to 190', rock bridge
from 190' to 180', and cemented with 25 sacks. Hole was filled with mud to
40', rock bridge from 40' to 30', and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 9/4/65
INV. NO. 1956-W