

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-049-20383-00-00

LEASE NAME Cory Rathman

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

NE SE NE Ft. from S Section, Line

 Ft. from E Section Line

SEC. 17 TWP. 30 RGE. 9 (E) or (W)

COUNTY Elk

LEASE OPERATOR Perkins Oil Company

ADDRESS Route # 2 Box 707 Howard, Kansas 67349

PHONE# (316) 374-2133 OPERATORS LICENSE NO. 4448

Date Well Completed 3-6-76

Character of Well oil

Plugging Commenced Jan. 25, 1995

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed Jan. 26, 1995

The plugging proposal was approved on January 18, 1995 1:30 P.M. (date)

by Jim Cheevers (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? yes

Producing Formation Depth to Top Bottom T.D. 2585'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	150'			8 5/8"		
	2584'			4 1/2"		750'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set bottom bridge @ 2475'. Mixed and dumped 5 sacks of cement.

Set bridge @ 750'. Cemented to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Long Drilling Company License No. 6112

Address Box 131 Hamilton, Kansas 66853

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Perkins Oil Company

STATE OF Kansas COUNTY OF Greenwood, ss.

Employee of Long Drilling Company (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Cory Rathman

FEB 07 1995

(Address) Box 131 Hamilton, Kansas 66853

WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 6 day of February, 1995



My Commission Expires: March 4, 1998

Notary Public

DRILLERS LOG

OPERATOR: Perkins Oil Company - Route 1 - Howard, Kansas 67349

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name: Cory Rathman Well No. 2

Sec. 17 T. 30 R. 9E Spot NE SE NE

County Elk State Kansas Elevation

Casing Record:

Surface: 8 5/8" @ 150' with 80 Sxs. 3% CC

Production: 4 1/2" @ 2584' with 75 Sxs.

Type Well: Oil Total Depth: 2585' K.B.

Drilling Commenced: 3-2-76 Drilling Completed: 3-6-76

Formation	From	To	Tops
Cellar	0	7	Kansas City 1740
Lime	7	150	Mississippi 2521
Shale & Lime (Stks)	150	1056	
Shale	1056	1274	
Lime	1274	1280	
Sand	1280	1330	
Lime & Shale	1330	1386	
Lime	1386	1570	
Shale	1570	1718	
Sand & Shale	1718	1740	
Lime	1740	1962	
Shale & Lime	1962	2130	
Shale & Lime (Stks)	2130	2521	
Lime	2521	2585	

COMPLETION RECORD

Liner Record: Size From To

Cementing Record: Sacks

Perforating Record:

Formation Date Number Shots

Initial Production:

Electric Log

Depths Covered

RECEIVED
STATE CORPORATION COMMISSION
FEB 07 1995
CONSERVATION DIVISION
WICHITA, KANSAS