

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR 15-009-05022-0000
FORMATION PLUGGING RECORD Strike out upper line when reporting plugging of formations.

NORTH

Locate well correctly on above Section Plat

Barton County Sec. 21-Twp. 16 Rge. (E) 11 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NW, NE S W
Lease Owner Franco Central and Hinkle Oil Company
Lease Name Seyfert Well No. 1
Office Address 919 Union National Bank Bldg., Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) D. & A.
Date well completed Nov 3, 1947 19
Application for plugging filed Nov. 3, 1947 19
Application for plugging approved Nov 3, 1947 19
Plugging commenced 11-4-47 19
Plugging completed 11-4-47 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	292'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

filled with mud to 283' 292'
set wood plug at 292
cemented with 15 sax of cement
mud to 15' below surface
set wood plug
cemented with 10 sax cement.

REC'D
DEC 6 - 1947 12-06-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hinkle Oil Company
Address 919 Union National Bank Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. B. Hinkle (employee or owner or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Hinkle
(Address)

SUBSCRIBED AND SWORN to before me this 3 day of December, 19 47

Murriel A. Upton
Notary Public.

My commission expires Jan 17 - 1950

PLUGGING
FILE SEC 21 T 16 R 116
BOOK PAGE 145 LINE 41

Casing record.
8 5/8" 292

Seyfert No. 1. NW 1/4 SW 1/4 21-16-11 Barton Co. Kansas.
Company: Franco Central Oil Co. & Hinkle Oil Company.
Contractor: J. B. Hinkle.
Commenced 10-25-47 Completed 11-3-47
Elevation 1896

0	240	surface clay & shells
240	280	sand & gravel
280	292	shale and red bed
292	350	shale and shells
350	435	sand and shale
435	730	shale and shells
730	755	Anhydrite
755	1980	shale and shells
1980	2120	shale and lime
2120	2470	shale
2470	2530	shale and lime
2530	2640	shale and shells
2640	2845	shale and lime
2845	3105	lime
3105	3150	lime and shale
3150	3162	soft lime
3162	3280	lime
3280	3324	lime and shale
3324	3360	lime
3360	3392	cherty conglomerate
3392	3402	Dolomite
Tops:		
K. C.	3052	
Arb.	3392	

State of Kansas)
) ss
County of Sedgwick)

I hereby certify that the above is a true and correct log as compiled from the daily drilling reports kept on said well.

J. B. Hinkle

Subscribed and sworn to before me this 10th day of November, 1947.

Muriel A. Lupton
M.P.

My commission expires 1-17-50

PLUGGING
FILE SEC 21 T 16 R 11W
BOOK PAGE 145 LINE 41

