


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

FORMATION PLUGGING RECORD

OR 15-009-30874-0000
Strike out upper line when reporting plugging of formations.

Barton County, Sec. 21 Twp. 16S Rge. 11W (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW NE NE
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Laudick Well No. 1
Office Address Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 20, 1947
Application for plugging filed Verbal December 20, 1947
Application for plugging approved Verbal December 20, 1947
Plugging commenced December 20, 1947
Plugging completed December 20, 1947
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Kerr
Producing formation Depth to top Bottom Total Depth of Well 3408 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	314	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 310 feet.
Set Halliburton bridging plug at 310 feet and plugged with 15 sacks of cement.
Filled with heavy mud to 10 feet. Bridged hole at 10 feet and plugged with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corporation
Address Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick
M. W. Smith (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature] 12-23-47

Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of December 1947

[Signature]
Patricia Meeker
Notary Public.

My commission expires January 21, 1950



Laudick #1
Sec. 21-16S-11W,
Barton County, Kansas
Anderson-Prichard Oil Corporation

Commenced: December 6, 1947
 Completed: December 21, 1947

Shale and shells	0	525
Red bed and shells	525	740
Anhydrite	740	770
Shale and shells	770	1410
Lime and shale	1410	1585
Shale and lime streaks	1585	1800
Lime	1800	1950
Lime and shale	1950	2190
Lime	2190	2330
Shale	2330	2485
Lime and shale	2485	2890
Lime	2890	3351
Conglomerate	3351	3395
Lime	3395	3408
TOTAL DEPTH		3408

CASING RECORD

8-5/8" casing set at 319' and cemented with 200 sacks of cement.

STATE OF OKLAHOMA)
)
 COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of your Laudick No. 1 Well, located in Section 21, Township 16 South, Range 11 West, Barton County, Kansas.

HELMERICH & PAYNE, INC.

By William D. Hoover
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 5th day of January, 1948.

Sheila Stiffen
 Notary Public

My commission expires July 28, 1951.

JAN 9 - 1948

PLUGGING
 FILE SEC 21-16-R-116
 BOOK PAGE 6 LINE 11