


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 21 Twp. 16 Rge. 11 (~~E~~ W) (W)  
Location as "NE/CNW%SW%" or footage from lines NW SW NW  
Lease Owner Duke Drilling Company  
Lease Name Perdue Well No. 1  
Office Address P.O. Box 123, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed June 19 39  
Application for plugging filed February 23 19 61  
Application for plugging approved " 19 61  
Plugging commenced February 23 19 61  
Plugging completed February 27, 19 61  
Reason for abandonment of well or producing formation loss of production.



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production October 19 60  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan - Russell, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3351 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 2336' to 2316'.  
Dumped 5 Sacks cement from 2316' to 2276'. Cleaned out cellar. Set in jacks. Pulled 12" tension at 100,000# pressure.  
Made shots at 2280', 2000', 1700' and 1600'. Pulled pipe.  
Mudded hole to 360'. Set 10' rock bridge from 360' to 350'.  
Mixed and dumped 25 sacks cement from 350' to 275'. Mudded hole.  
Mudded hole to 40'. Set 10' rock bridge from 40' to 30'.  
Mixed and dumped 10 sacks cement from 30' to base cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
leo

03-08-61 MAR 8 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.  
Address P.O. Box 304 - Great Bend, Ks.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Lewis O. Chubb (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lewis O. Chubb  
Lewis O. Chubb  
Box 123, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of March, 19 61

My commission expires June 24, 1961

Clair E. Stimson  
Clair E. Stimson Notary Public.