

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-009-19252-0000

LEASE NAME Seyfert

WELL NUMBER 4

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 21 TWP. 16 RGE. 11 (W) (W)

COUNTY Barton

Date Well Completed Spud 2-27-46

Plugging Commenced 3-28-96

Plugging Completed 3-29-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Eason Drilling Services

ADDRESS 2 West Second St. -Tulsa. Ok. 74103

PHONE#(918) 583-1791 OPERATORS LICENSE NO. 30151

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3369'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	213'	none
				5 1/2"	3363'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet. Set bridge plug at 2706'. Perforated well at 1475', @750' and 250'. Ran tubing to 1500', pumped 160 sacks 60/40 POZMIX 10% gel cement. Pulled tubing to 250' and pumped 40 sacks cement (60/40 POZMIX 10% gel), circulated to surface. Tied on to 8-5/8" surface. Well pressured up, backside was squeezed. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Eason Drilling Services -Tulsa. Ok.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 1st day of April, 19 96

Jane Derrberg  
Notary Public

My Commission Expires:



Form 05-  
Revised 05-