

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-055-10021-0000  
 Completion 4-20-56

LEASE NAME Sooby

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 27 TWP. 22 RGE. 33W (E) or (W)

COUNTY Finney

Date Well Completed         

Plugging Commenced 7-2-97

Plugging Completed 7-3-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Lebsack Oil Production, Inc.

ADDRESS P. O. Box 489 Hays, KS 67601-0489

PHONE (913) 625-5444 OPERATORS LICENSE NO. 5210

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4777'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4	347'	none
				5 1/2	4776'	1213'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each section. Sanded bottom to 4654' & ran 5 sks cement. Shot at 1213', worked pipe free. Pulled 1 it. Mixed 13 sks gel, then 80 sks cement at 1200'. Pulled to 700', mixed 30 sks cement. Pulled to 380', mixed 90 sks cement. Pulled rest of pipe & topped with 20 sks. Plugging complete. 60/40 6%

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 81529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lebsack Oil Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 97

My Commission Expires:         



RECEIVED  
 KANSAS CORP COM  
 1997 JUL 15 4 11:23 PM