

15-055-10011-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1-8-54LEASE NAME Adams SWDWELL NUMBER 1 Ft. from S Section Line Ft. from E Section LineSEC. 27 TWP. 22 SRGE. 33 (E) or (W)COUNTY FinneyDate Well Completed Plugging Commenced 12/15/89Plugging Completed 12/22/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Union Pacific Resources CompanyADDRESS P.O. Box 7 - MS 3407, Fort Worth, TX 76101-0007PHONE#(817) 877-7956 OPERATORS LICENSE NO. 6417Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/15/89 (date)by Richard Lacey & Mike Stang (KCC District Agent's Name).Is ACO-1 filled? Yes If not, is well log attached? Producing Formation Did Not Produce Depth to Top Bottom T.D. 4897'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	352'	5'
				7"	4896'	5'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mix & spot 50 sx 60/40 POZ w/6% @ 980' to 700', spot gel 700' to 350'. Spot 65 sx 60/40 POZ w/6% Gel from 380' to surf. Procedure called for pumping 100 sxs 65/35 Lite. Mixed 50 sx. Had returns in cellar. Pumped remaining 20 sxs to clear tubing. Plugging witnessed by Case Morris.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. Address Wichita, KS Colorado Derby Bldg., Ste 600 (Division Office)NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources CompanySTATE OF Texas COUNTY OF Tarrant, ss.Joy L. Prohaska

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joy L. Prohaska(Address) P.O. Box 7 - MS 3407, TX 76101-0007SUBSCRIBED AND SWORN TO before me this 9 day of January, 19 90My Commission Expires: May 23, 1993